



**CAPITAL PROGRAM  
SERVICES 5750 ALMADEN  
EXPRESSWAY SAN JOSE,  
CA 95118-3686 TELEPHONE  
(408) 630-3004  
FACSIMILE (408) 979-5631  
www.valleywater.org  
scvwdplanroom@valleywater.org**

*Notification of this Addendum is transmitted via email to all current plan holders.  
This Addendum is posted on the District website  
at  
www.valleywater.org/Programs/Construction.aspx.*

May 26, 2016

**ADDENDUM NO. 1  
TO CONTRACT DOCUMENTS FOR THE  
REGNART CREEK EROSION REPAIR PROJECT  
Project No. 62084001, Contract No. C0615**

Notice is hereby given to Prospective Bidders that the Contract Documents are modified as hereinafter set forth.

**BID DOCUMENTS**

Notice to Bidders

**REPLACE** Item 6.B. in the Notice to Bidders with:

**“Supplemental Bid Items.** These Bid Items may or may not be required. They may be deleted entirely or in part, by deductive change order(s), at the sole discretion of the District. The sum of the Total Base Bid and the Total Supplemental Bid will be used to determine the lowest Bid price.”

**SPECIFICATIONS AND CONTRACT DOCUMENTS**

**SPECIAL PROVISIONS**

**Section 11. WORK AND SCHEDULE OF WORK**

**Article 11.07 Liquidated Damages**

**DELETE** Paragraph A.5. in its entirety.

**DELETE** Paragraph A.6. in its entirety.

**Section 14. GENERAL COORDINATION**

**Article 14.04. Construction Survey**

**ADD** text after second sentence of sixth paragraph of Paragraph H. as follows:

“Rock elevation will be considered as subgrade for embankment areas requiring placement of embankment fill above rock.”

## **TECHNICAL PROVISIONS**

### **Section 22. PREPARATORY WORK**

#### **Article 22.06. Non-Native Tree Removal – Bid Item No. 7**

**REPLACE** the title of article “22.06.03. Measurement” with:

“22.06.04. Measurement”

**REPLACE** the title of article “22.06.04. Payment” with:

“22.06.05. Payment”

### **Section 23. EARTHWORK**

#### **Article 23.01.02.07 Payment**

**REPLACE** text in Paragraph A. that reads “. . . per cubic yard . . .” with:

“. . . per Compacted (in-place) Cubic Yard . . .”

## **GENERAL QUESTIONS & RESPONSES**

**QUESTION 1.** When is the work expected to be completed?

**RESPONSE 1.** October 15, 2016.

**QUESTION 2.** What is the water surface elevation for the 100-year event?

**RESPONSE 2.** Historical stream gage data can be downloaded from our website at <http://valleywater.org/Services/Alert.aspx>

**QUESTION 3.** Can the trees be chipped and used as mulch in the creek?

**RESPONSE 3.** See Article 22.06.03 Placement.

**QUESTION 4.** Besides rainfall, are there any other sources of water that flow into the creek?

**RESPONSE 4.** Stevens Creek Pipeline, West Valley Pipeline, SD outfalls.

**QUESTION 5.** If a pipeline breaks, will water flow into the creek?

**RESPONSE 5.** Yes.

**QUESTION 6.** Is damming the creek allowed for the purpose of dewatering?

**RESPONSE 6.** See Article 22.03 Control of Water – Bid Item No. 3.

**QUESTION 7.** How is the channel accessed for the removal of trees?

**RESPONSE 7.** Access is as shown in the plans.

**QUESTION 8.** Can contractors clear the brushes to access the trees?

**RESPONSE 8.** See Article 22.02 Clearing and Grubbing.

**QUESTION 9.** Will the District mitigate the trees?

**RESPONSE 9.** All mitigation related to the removal of trees shown on the plans have been accounted for by the District.

**QUESTION 10.** Are the contractors responsible if the bank is damaged when the big trees are removed? There is a possibility of a vertical deep gap.

**RESPONSE 10.** See Article 22.06.03. Placement.

**QUESTION 11.** Can the contractors store their equipment on the ramp or pull their equipment back to the top of the channel at the end of the day?

**RESPONSE 11.** No construction equipment is to be left within the channel overnight.

**QUESTION 12.** What time is the work allowed to begin in the morning and what are the sound level requirements for the residential area?

**RESPONSE 12.** See Article 17.03 Noise Pollution and Vibration Monitoring.

**QUESTION 13.** Is all the fencing alongside November Drive staying, or can it be removed and put back after the work is complete?

**RESPONSE 13.** See Articles 6.13 and 15.07.

**QUESTION 14.** Does all the excavated material need to be hauled off, or can it be reused?

**RESPONSE 14.** See Articles 23.01.02.02 and Section 23.02. Also refer to the Drawings.

**QUESTION 15.** Is the rock from Stevens Creek Quarry required to meet Caltrans specifications?

**RESPONSE 15.** See Section 24 Rock Slope Protection.

**QUESTION 16.** Can the contractors re-walk the creek site to gain a better understanding of the project?

**RESPONSE 16.** No additional pre-bid conferences will be conducted.

**QUESTION 17.** Are two (2) layers of 1/2-Ton rock required within the Rock Cross Vane structure throughout?

**RESPONSE 17.** No, placement of 1/2-Ton rock can be reduced to one (1) layer within the deepest portion of the pool to establish a 0.5' vertical clearance between the top of rock within the pool and concrete slab at downstream limit of project as shown on the plans.

THIS ADDENDUM NO. 1, WHICH CONTAINS 4 PAGES, IS ATTACHED TO AND IS A PART OF THE SPECIFICATIONS AND CONTRACT DOCUMENTS FOR THIS PROJECT.



Date:

5/26/16

Saeid Hosseini, P.E.  
Engineering Unit Manager (acting for)  
Melanie Richardson, P.E.  
Deputy Operating Officer  
Watershed Capital Division